



Republic of the Philippines
 City of Cagayan de Oro
BIDS AND AWARDS COMMITTEE



REQUEST FOR QUOTATION
(Negotiated 53.1 of the 2016 Revised IRR of RA 9184 – Two Failed Biddings)

Date: 26 April 2024

 Name of Contractor

 Address

Gentlemen/Mesdames:

Please quote us your lowest price on the item/s listed below, for the project, Concrete Paving of Road at Sitio Tinipigan to Sitio Bonjoc, Dansolihon; SN 148b - 2023, and submit this Request for Quotation (RFQ) to the BAC, together with the following authenticated documents, not later than 2:00 P.M. of 02 May 2024 at the Bids and Awards Committee Conference Room, 3rd Floor Administrative Building, City Hall, Cagayan de Oro City, to wit:

1. PhilGEPS Certificate of Registration and membership (Platinum);
2. Omnibus Sworn Statement;
3. Organizational Chart for the project;
4. List of contractor’s personnel (viz: project manager, project engineers, material engineers, and foremen) be assigned to this project, with complete qualification and experience data;
5. List of contractor’s equipment units, which are owned, leased, and/or under purchase agreements, supported by certification of availability of equipment lessor/vendor for the duration of the project;
6. Duly signed Bill of Quantities; and
7. Duly signed Detailed Estimates

=====


ITEM	QTY.	UNIT	PARTICULARS	UNIT PRICE (PhP)	TOTAL PRICE (PhP)
Part A			Facilities for the Engineers		
A.1.1	3.30	mo.	Facilities for the Engineers		
Part B			Other General Requirements		
B.7(1)	3.30	mo.	Occupational Safety and Health Program		
B.5	4.00	each	Project Billboard/Signboard		
B.9	1.00	l.s.	Mobilization/Demobilization		
Part C			Earthworks		
102(2)	291.50	cu.m.	Surplus Common Excavation		
103(1)a	21.67	cu.m.	Structure Excavation (common soil)		
103(6)a	97.81	cu.m.	Pipe Culverts and Drain Excavation		
105(1)a	11,656.00	sq.m.	Subgrade Preparation		
Part D			Base and Subbase Course		
200(1)	2,331.20	cu.m.	Aggregate Sub-base Course, t=200mm		

201(1)a	874.20	cu.m	Aggregate Base Course, t=100mm		
201(1)b	874.20	cu.m.	Aggregate Base Course, t=300mm		
Part E			Surface Course		
311(1)b1	8,742.00	sq.m.	PCC Pavement (Carriageway, t=200mm)		
Part F			Minor Structures		
405(1)a2	0.84	cu.m.	Structural Concrete, Class "A" (3000psi)		
407(1)	1.29	cu.m.	Lean Concrete, Class "B"		
Part G			Drainage and Slope Protection		
500(1)a1	63.00	ln.m.	Pipe Culverts, 610mm dia (24"Ø)		
505(1)b	3.36	cu.m.	Riprap Class "B"		
506 (1)	25.80	cu.m.	Stone Masonry		
				Grand Total	

Note:

1. The Project Duration is One Hundred Ten (110) Calendar Days.
2. The Contractor must be *PhilGEPS* registered.
3. Price Quotation must be *inclusive of Tax*.
4. Successful contractor shall post *performance and warranty securities* prescribed in Section 39 and 62 of the 2016 Revised Implementing Rules and Regulations of the Republic Act 9184.

By Authority of the BAC:



ATTY. JOEFFREY D. NAMALATA
BAC Chairperson

Received by:

Name of Contractor

Printed Name and Signature of the Authorized Signing Official

Telephone/Cellphone No.

PhilGEPS Certificate Number